

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20879-00-00
Spot: NWSE Sec/Twnshp/Rge: 25-28S-19W
2047 feet from S Section Line, 1956 feet from E Section Line
Lease Name: VIEUX Well #: 1
County: KIOWA Total Vertical Depth: 4925 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N STE1010D
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	499		WITH 125 SX CMT
PROD	4.5	4928	2030	WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/21/2011 10:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: B. LYNN HERRINGTON Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: SAND TO 4870' & 4 SX CMT. 1ST PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 520' WITH 10 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. CMT CIRCULATED.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2011 11:35 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND TO 4870' & 4 SX CMT. 1ST PLUG AT 1260' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4917	4921		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED

DEC 05 2011

KCC WICHITA

District: 01

Signed Eric McLaren
(TECHNICIAN)

RECEIVED

DEC - 1 2011

KCC DODGE CITY

Form CP-2/3

12/07/11