

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-02204-00-01

Spot: N2SWSE

Sec/Twnshp/Rge: 10-18S-18W

990 feet from S Section Line, 1980 feet from E Section Line

Lease Name: KRUG A

Well #: 2

County: RUSH

Total Vertical Depth: 3934 feet

Operator License No.: 5447

String Size

Depth (ft)

Pulled (ft)

Comment

Op Name: OXY USA INC.

SURF

1227

WITH 500 SX CMT

Address: 5 E GREENWAY PLZ PO BOX 27570

L1

3920

132' W/50 SX CMT

HOUSTON, TX 77227

PROD 5.5

3822

0

WITH 100 SX CMT

Well Type: SWD

UIC Docket No: D04734.0

Date/Time to Plug: 11/19/1983 12:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from:

Company:

Phone:

Proposed
Plugging
Method:

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed: 12/04/1983 12:00 AM

KCC Agent: STEVE DURRANT

Actual Plugging Report:

11/22/83: FOUND TBG DEPTH @ 25'. RAN 175' OF 3/4" RODS DOWN 5 1/2".
(COULDN'T GET ANY DEEPER). 11/23/83: RAN 5/8" RODS DOWN 8 5/8" X 5 1/2"
ANNULUS TO 140'. (COULDN'T GO ANY DEEPER.) 11/30/83: RAN 1 5/8" MILL TO
170'. MILL WENT OUT 5 1/2" CASING. 12/1/83: RAN 4 7/8" MILL W/WASH PIPE TO
100'. NO CIRCULATION, CAME OUT WITH CASING BUT NO TUBING. 12/2/83: RAN
3 3/4" BIT. COULDN'T GET PAST 50' & NO CIRCULATION. CASING PARTED AT 50'.
12/3/83: PUMPED 100 SX CMT DOWN 8 5/8" CASING AND CEMENT CAME OUT OF
THE GROUND 8' FROM WELLHEAD. MAXIMUM PRESSURE WAS 150 PSIG. 12/4/83:
CMT TOP AT 12' COMPANY TOPPED OFF THE WELL WITH REDI MIX.

Perfs:

Top	Bot	Thru	Comments
3920	3934	OH	

Remarks: **WELL WAS PLUGGED DUE TO ITS INABILITY TO PASS MIT REQUIREMENTS** HALLIBURTON
PUMPED 60/40 POZMIX W/10 SX GILSONITE CMT.

Plugged through: CSG

RECEIVED

DEC 05 2011

District: 01

Signed

Steve Durrant

(TECHNICIAN)

KCC WICHITA

RECEIVED

DEC -1 2011

KCC DODGE CITY

12/07/11
Form CP2/3

cc to MIC 12/05/11