

1 090463

8-25

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,988 -00-00

C NE SE, SEC. 31, T 20 S, R 25 W

12-13-11 ^{Perms} 1980 1954 feet from S section line
660 669 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

Lease Name McVicker Well # 1

Operator: Vess Oil Corporation

County Ness 158.76

Name & Address 8100 E. 22nd St. N, Bldg. 300

Well Total Depth 4885 feet

Wichita, KS 67226

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 614

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address Rt. 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 25 Month: 8 Year: 19 94

Plugging proposal received from Mike Kasselmann

(company name) Vess Oil Corporation (phone) 316-793-3051

Work: 5 1/2" at 4661' w/150 sx cement, PBSD 4410', Perfs at 4374-79', DV tool @ 1585' w/300 sx cmt.
1st plug pump 300 lbs. hulls and cement to 4379',

Check backside.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:10 p.m. Day: 25 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 300 sx cement down 5 1/2" casing.

Maximum pressure 800 psi and shut in 300 psi.

No connection to get into backside. Will check cement top when head is cut off.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of form.)

INVOICED

DATE SEP 12 1994

INV. NO. 41201

STATE CORPORATION COMMISSION RECEIVED
AUG 29 1994
CONSERVATION DIVISION
WICHITA, KANSAS
Signed [Signature]