

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20602-00-00
Spot: NESESENW Sec/Twnshp/Rge: 24-25S-31W
3275 feet from S Section Line, 2656 feet from E Section Line
Lease Name: BEACH Well #: 2
County: FINNEY Total Vertical Depth: 2630 feet

Operator License No.: 33358
Op Name: RENICK ENERGY, L.C.
Address: 10502 6 RD
INGALLS, KS 67853

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1611		WITH 800 SX CMT
PROD	4.5	2629	0	WITH 425 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/17/2011 10:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 300# HULLS & 20 SX CMT. SPACER TO 1750'. PLUG AT 1750' WITH 25 SX CMT. SPACER TO 1100'. CMT FROM 1100' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2011 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 250# HULLS & 50 SX CMT FROM 2568' TO 1500'. PUMP 6 BBL SPACER TO 1100'. PUMP 85 SX CMT FROM 1100' TO 0'. PRESSURE TO 600#. HOLDING. PUMP 15 SX CMT DOWN ANNULUS TO 400#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2562	2568		
2548	2556		
2522	2526		

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED
DEC 08 2011
KCC WICHITA

RECEIVED
NOV 30 2011
KCC DODGE CITY

Form SP-73

12/14/11