

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-00212-00-00  
Spot: NWNWNWSE Sec/Twnshp/Rge: 17-22S-31W  
2540 feet from S Section Line, 2540 feet from E Section Line  
Lease Name: NEUMANN Well #: 1  
County: FINNEY Total Vertical Depth: 2765 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2610		WITH 2 SX CMT
SURF	10.75	344		WITH 250 SX CMT
PROD	5.5	2762	0	WITH 700 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2011 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed  
Plugging  
Method:

CIBP @ 2610' WITH 2 SX CMT. CIRCULATE CASING WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/21/2011 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:


Perfs:

CIBP @ 2610' WITH 2 SX CMT. CIRCULATE 5 1/2" CASING FULL OF CMT THROUGH TBG FROM 1340' TO 0' USING 150 SX CMT. FILL ANNULUS USING 25 SX CMT.

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY ALLIED. RECEIVED DEC 08 2011  
Plugged through: TBG KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

NOV 30 2011

KCC DODGE CITY

Form CP-29

12/14/11