

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21340-00-00
Spot: SWSE Sec/Twnshp/Rge: 3-23S-21W
660 feet from S Section Line, 1839 feet from E Section Line
Lease Name: KINGRY Well #: 1-3
County: HODGEMAN Total Vertical Depth: 5060 feet

Operator License No.: 34255
Op Name: JRC PRODUCTION, LLC
Address: 746 E 520TH AVE
PITTSBURG, KS 66762

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	293		
DVT		1405		
PROD	4.5	4742	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/25/2011 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JIM EWERS Company: JRC PRODUCTION Phone: (918) 845-4463

Proposed Plugging Method: BOTTOM PLUG: RUN TBG TO 4400' & SPOT 50# HULLS & 20 SX CMT. TOP PLUG: PULL TBG TO 1400' & CIRCULATE CMT TO SURFACE. PRESSURE TEST 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2011 3:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

BOTTOM PLUG: RAN TBG TO 4408' & PUMPED 50# HULLS WITH 20 SX CMT. NO GEL WAS ORDERED FOR PLUGGING. TOP PLUGS: PULLED TBG TO 1395'. PUMPED 150 SX CMT DOWN THE TBG CIRCULATING CMT TO SURFACE UP THE 4 1/2". PULLED TBG OUT OF HOLE. PUMPED 130 SX CMT DOWN 4 1/2" AND COULD NOT FILL UP THE 4 1/2". PUMPED 30 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS AND BLEW A HOLE IN THE 8 5/8". COMPANY DISAPPEARED FOR 3 YEARS. 11/4/11: PUMPED 69 SX CMT DOWN 4 1/2" AND FILLED IT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4568	4576		

Remarks: COPELAND PUMPED 60/40 POZMIX 4% GEL ON 11/25/08. ALLIED PUMPED 60/40 POZMIX 4% GEL ON 11/4/11.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey

(TECHNICAL) RECEIVED

RECEIVED
DEC - 1 2011
KCC DODGE CITY

DEC 08 2011
KCC WICHITA

12/14/11