

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01313-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 2-34S-15W
1839 feet from S Section Line, 4490 feet from E Section Line
Lease Name: DAVIS Well #: 4(1)
County: BARBER Total Vertical Depth: 4899 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	296		WITH 175 SX CMT
PROD	4.5	4891	780	WITH 75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2011 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KENNETH WERNER Company: _____ Phone: (785) 623-4081

Proposed Plugging Method: SAND BACK TO PERFS & 4 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 320' WITH 75 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: JACK MACCLASKEY Witness Type: NONE
Date/Time Plugging Completed: 11/30/2011 11:45 AM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

SAND BACK TO 4020' & 4 SX CMT. 1ST PLUG AT 709' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 324' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4070	4074		CHEROKEE SAND

Remarks: USED 60/40 POZMIX 4% GEL BY QULALITY.

Plugged through: CSG

District: 01

Signed

Jack MacClaskey
(TECHNICIAN)

RECEIVED
DEC - 1 2011
KCC DODGE CITY

RECEIVED
DEC 08 2011
KCC WICHITA

FORM CR 2/3

12/14/11