

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00360-00-01
Spot: SEWNWE Sec/Twnshp/Rge: 4-23S-15W
4344 feet from S Section Line, 1645 feet from E Section Line
Lease Name: CHESTER Well #: 3
County: PAWNEE Total Vertical Depth: 4154 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3997		WITH 2 SX CMT
SURF	8.625	955		WITH 550 SX CMT
PROD	5.5	4152	0	WITH 180 SX CMT

Well Type: SWD UIC Docket No: D04964.0 Date/Time to Plug: 11/18/2011 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TRACEY HOLLIS Company: HERMAN L. LOEB Phone: (618) 943-2227

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 11/21/2011 10:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

11/18/11: SET CIBP @ 3997' & 2 SX CMT. 2ND PLUG PERFORATE 5 1/2" CASING AT 990'. ESTABLISH CIRCULATION, PUMPED 350 SX CMT TO SURFACE. CMT DROPPING IN CASING. SDFN. 11/21/11: 3RD PLUG TAG TOC @ 370'. PERFORATE 5 1/2" CASING AT 320'. CIRCULATE CMT TO SURFACE WITH 95 SX CMT. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4051	4061		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
NOV 21 2011
KCC DODGE CITY

cc to UIC 12/08/11

RECEIVED
DEC 08 2011
KCC WICHITA

Form CP 2/3
12/14/11