

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20853-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 27-16S-33W
1333 feet from N Section Line, 1672 feet from E Section Line
Lease Name: RINER Well #: 1-27
County: SCOTT Total Vertical Depth: 4830 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 221 | | WITH 165 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/24/2011 9:45 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TONY MARTIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1660' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 11/24/2011 12:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1660' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
DEC - 1 2011
KCC DODGE CITY

RECEIVED
DEC 08 2011
KCC WICHITA
12/14/11