

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19529-00-00  
Spot: SEWSE Sec/Twnshp/Rge: 23-28S-5E  
1335 feet from S Section Line, 1665 feet from E Section Line  
Lease Name: NORTH FOX BUSH-SHAWVER Well #: 2  
County: BUTLER Total Vertical Depth: 2814 feet

Operator License No.: 32475  
Op Name: BRADEN, JAMES R. DBA BRADEN PET  
Address: 10139 SW HAVERHILL RD  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	2504		
LI	4.5	2680		
PROD	5.5	2754		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2011 8:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER  
Date/Time Plugging Completed: 11/10/2011 5:00 PM

Witness Type: PARTIAL  
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS @ 2675', DUMP BAILED 4 SXS CEMENT ON TOP. RIH W/TBG ON BACKSIDE @ 55'. CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TBG. RIH W/TBG @ 250', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 27 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11-10-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #34095.

Perfs:


Top	Bot	Thru	Comments
2754	2814	OH	OPEN HOLE

Remarks: LANDOWNER COMPLAINT, CEMENT TICKET #31709 ON 4-1/2" LINER

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED Form CP-2/3

DEC 08 2011

12/14/11

JK

KCC WICHITA