

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40056-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 26-28S-5E
3485 feet from S Section Line, 2293 feet from E Section Line
Lease Name: NORTH FOX BUSH-WEBSTER Well #: S-4
County: BUTLER Total Vertical Depth: 3500 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	3221		1050 SX
COND	#####	1306		1320 SX
PROD	5.5	900		550 SX

Well Type: SWD UIC Docket No: D15656.0 Date/Time to Plug: 11/10/2011 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JAMES R. BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2011 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

WASHED AND CIRCULATED HOLE CLEAN @ 1450'. LAYED DOWN WORKSTRING. RIH OPEN ENDED TO GET TALLY ON TBG, COULD ONLY RUN INTO @ 1175' (OUTSIDE CASING). LAYED DOWN TBG. DUMPED W/FLUID 50 GAL SAND ON BOTTOM. RIH W/TBG @ 1175', CONSOLIDATED MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 1% CC & DISPLACED IN CASING. WAITED 2 HOURS FOR CEMENT TO SET UP, TAGGED CEMENT @ 1250'. RIH W/TBG @ 250', CONSOLIDATED ESTABLISHED CIRCULATION AND MIXED & PUMPED 36 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:00 PM 11-10-2011. CONSOLIDATED CEMENT TICKET # 34094.

Perfs:

Top	Bot	Thru	Comments
3221	3500	OH	OHIO

Remarks: FAILED MIT TEST / COULD NOT REPAIR. DUG OUT SURFACE BEFORE PLUGGING, ALL STRINGS OF PIPE HAD CEMENT @ SURFACE.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

cc to UIC 12/08/11

RECEIVED
Form CP-2/3
DEC 08 2011 12/14/11
KCC WICHITA

12