

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10805-00-00
Spot: W2NESW Sec/Twnshp/Rge: 27-21S-14W
2027 feet from S Section Line, 3609 feet from E Section Line
Lease Name: GATES B Well #: 5
County: STAFFORD Total Vertical Depth: 3752 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3480		WITH 2 SX CMT
SURF	8.625	275		WITH 200 SX CMT
PROD	5.5	3749	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/29/2011 2:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 3480' WITH 2 SX CMT. PERFORATE 5 1/2" @ 780'. RUN TBG TO 780' & CIRCULATE CMT UP 5 1/2" AND 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/29/2011 4:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3480' & 2 SX CMT WITH DUMP BAILER. PERFORATED 5 1/2" @ 780'. RAN TBG TO 779'. PUMPED 125 SX CMT DOWN TBG & CIRCULATED CMT TO SURFACE. SHUT IN 5 1/2" CASING & PRESSURED IT TO 500 PSIG. NO ENTRY INTO 8 5/8" X 5 1/2" ANNULUS. PULLED TBG OUT OF HOLE. TOPPED OFF 5 1/2" WITH 10 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3571	3576		
3552	3557		
3531	3536		

Remarks: **COMPLIANCE ISSUE: DENIED TA FL NOT SHOT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

DEC - 2 2011

KCC DODGE CITY

RECEIVED

DEC 08 2011

KCC WICHITA

Form CP-2/3

12/14/11