

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23789-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 11-9S-25W
990 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SCHAMBERGER Well #: 11-1
County: GRAHAM Total Vertical Depth: 4145 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	275		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/03/2011 12:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: BRAD Company: H&C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 12/03/2011 8:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 2265' w/25 sxs.
2nd. Plug at 1345' w/100 sxs.
3rd. Plug at 325' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
DEC 09 2011
KCC WICHITA

Form CP-2/3

✓ 12/14/11

DEC 06 2011