

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24752-00-00  
Spot: NENWNWSW Sec/Twnshp/Rge: 21-20S-23W  
2461 feet from S Section Line, 511 feet from W Section Line  
Lease Name: PETERSILIE-BECHTHOLD LN Well #: #1-21  
County: NESS Total Vertical Depth: 4350 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	207		CEMENTED WITH 160 SX CMT
PC		1506		CEMENTED WITH 130 SX CMT. 10 SX TO PIT.
PROD	5.5	4343	0	CEMENTED WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2011 10:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-5116

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 20 SX CMT & HULLS. PULL TBG TO 1500' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2011 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4224' & PUMPED 35 SX CMT & 200# HULLS. PULLED TBG TO 1500' & PUMPED 160 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 15 SX CMT. STAYED FULL. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier  
(TECHNICIAN)

RECEIVED  
NOV 30 2011  
KCC DODGE CITY

RECEIVED  
DEC 12 2011  
KCC WICHITA

Form CP-2/3

12/14/11