

To: 1 051472
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-25
API NUMBER 15- 171-20,062-00-00 162
C NW, SEC. 18, T 19 S, R 31 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3857

Operator: Unico Inc./Inter Mountain Chem. Inc.
Name:
Address: P.O. Box 69
Commerce City, CO 80022

3960 feet from S section line
3960 feet from E section line

Lease Name B.S. Yager Well # 1
County Scott 104.00

Well Total Depth 3200 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 9:30 a.m. Day: 25 Month: 9 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service (phone) 316-675-8349

were: 5 1/2" at 2853' w/150 sx cement, PBTD 2800', Perfs at 2765-2771' Tubing fish top at 1900'

1st plug pump 2 sx hulls and 25 sx cement,

2nd plug at 1400' with 80 sx cement,

3rd plug at 300', circulate to top.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 p.m. Day: 25 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 1900',

Spot through casing:

2nd plug at 1400' with 80 sx cement,

3rd plug at 300-0', circulated cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 01 1991

Remarks: Used common cement by Midwest. Recovered 1783' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-23-91
INV. NO. 33422

Signed Richard W. Lucy (TECHNICIAN)