

To: 1 051350
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-30 API NUMBER 15- 171-20,126 -00-00 267P
C SW, SEC. 17, T. 19 S, R. 31 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3857
Operator: UNICO, Inc.
Name & Address 1921 Bloomfield Blvd.
Farmington, NM 87401

1320 feet from S section line
3960 feet from E section line
Lease Name Ely Well # 1-17
County Scott
Well Total Depth 2885 93.76 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 364
Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497
Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 30 Month: 4 Year: 19 92

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 2884', Perfs at 2754-60', Top of Permian 1400'

1st plug pump 200 lbs. hulls and 25 sx cement to 2600',
2nd plug perforate 4 1/2" at 1400' and pump 50 sx cement down 4 1/2" to 1300', displace with gel,
3rd plug perforate at 380' and pump cement down 4 1/2" casing and circulate cement up 8 5/8" X 4 1/2" annulus to surface.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:40 p.m. Day: 30 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement to 2600',
2nd plug perforated 4 1/2" at 1400' and pumped 50 sx cement down 4 1/2" to 1300', displaced w/gel,
3rd plug perforated at 380' and pumped 100 sx cement down 4 1/2" casing and circulated cement up 8 5/8" X 4 1/2" annulus to surface.

Remarks: Used common cement by Midwest. No casing recovery.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 5-15-92
INV. NO. 35251

Signed Richard M. Lacey (TECHNICIAN)

05-04-92
MAY 4 1992
STATE CORPORATION COMMISSION
CONSERVATION DIVISION