

To: 1 090107  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
206 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-9  
API NUMBER 15-171-20,430-00-00  
C SE NW, SEC. 12, T 19 S, R 31 W  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393  
Operator: A.L. Abercrombie, Inc.  
Name  
Address 150 N. Main, Suite 801  
Wichita, KS 67202

Lease Name Stucky Well # C-1  
County Scott 153.30  
Well Total Depth 4717 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie RTD, Inc. License Number 30684  
Address P.O. Box 56, Great Bend, KS 67530

Company to plug at: Hour: 7:30 a.m. Day: 9 Month: 8 Year: 19 91

Plugging proposal received from Tony Martin  
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2269-87'  
1st plug at 2300' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,  
3rd plug at 650' with 50 sx cement, 4th plug at 320' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:30 a.m. Day: 9 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement,  
2nd plug at 1300' with 80 sx cement,  
3rd plug at 650' with 50 sx cement,  
4th plug at 320' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 8-16-91

AUG 13 1991

Signed \_\_\_\_\_  
(TECHNICIAN)

INV. NO. 32745

CONSERVATION DIVISION  
WICHITA, KANSAS

