

1 050765

253  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,309-00-00  
SW NW \_\_\_\_\_, SEC. 11, T 19 S, R 31 W/4  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5393  
Operator: A. L. Abercrombie, Inc.  
Name & Address: 801 Union Center  
Wichita, KS 67202

Lease Name Steinberg Trust Well # 1  
County Scott 151.78  
Well Total Depth 4670 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 387

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 pm Day: 17 Month: February Year: 19 86

Plugging proposal received from Billy Fulls  
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4668' Perfs at 4614-4616  
1st plug sand back to 4570' and dump 5 sx cement on top of sand through bailer  
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 pm Day: 17 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4570' and dumped 5 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 15  
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 200 psi

Remarks: Recovered 1826' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 26 1986  
INV. NO. 12670

RECEIVED  
STATE CORPORATION COMMISSION  
Signed Richard W. Lacy  
(TECHNICIAN)  
FEB 24 1986