

1 070743

10-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,395-00-00
NE SW SW, SEC. 10, T 19 S, R 31 W/K
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886
Operator: Chief Drilling Company, Inc.
Name:
Address 224 East Douglas, Suite 350
Wichita, KS 67202

Lease Name Popp Well # 1
County Scott 151.39
Well Total Depth 4658 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883
Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 4:15 p.m. Day: 24 Month: 10 Year: 1989

Plugging proposal received from Marion Burris
(company name) Warrior Drilling Company (phone) 316-262-3791
Elevation 3950'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2168-89'
1st plug at 2200' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,
3rd plug at 280' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 6:15 p.m. Day: 24 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT Was stuck in hole at 3092', got loose with nitrogen

1st plug at 2200' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,
3rd plug at 280' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-30-89

INV. NO. 26263

10-24

Signed Dan Goodrow
(TECHNICIAN)

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10-12-89
month day year

NE SW SW Sec 10 Twp 19 S, Rg 31 East West
990 feet from South line of Section
4290 feet from East line of Section

OPERATOR: License # 5886
Name: Chief Drilling Co., Inc.
Address: 224 E. Douglas, #350
City/State/Zip: Wichita, KS 67202
Contact Person: Douglas W. Thimesch
Phone: 316 262-3791

County: Scott
Lease Name: Popp Well #: 1
Field Name: Wildcat

CONTRACTOR: License #: 5883
Name: Warrior Drilling Company

Is this a Prorated Field? yes no
Target Formation(s): Marmaton
Nearest lease or unit boundary: 990'
Ground Surface Elevation: N/A feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 125' 180'
Depth to bottom of usable water: 1300'
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 250'
Length of Conductor pipe required: none
Projected Total Depth: 4600'
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
 well farm pond other
DWR Permit #: 10129
Will Cores Be Taken?: yes no
If yes, proposed zone: _____

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OAWO Disposal Wildcat Cable
 Seismic; # of Holes

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____


Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location: _____

Exp. 4/11/90

200' Alt. II Req.

AFFIDAVIT

PUSHER _____
TD _____ FORMATION _____
SURFACE PIPE 8 5/8 @ 262
ANHYDRITE 2100' ELEVATION 2950'
STARTING TIME & DATE _____
COMPLETION TIME & DATE _____
1st PLUG @ 2200 FT. W/ 50 SX
2nd PLUG @ 1500 FT. W/ 70 SX
3rd PLUG @ 250 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ _____
CEMENT COMPANY _____
TECHNICIAN DG
TYPE OF CEMENT 60/40 6%



SPUD
10/13/89
85711-2501
RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1989
CONSERVATION DIVISION
Wichita, Kansas

Spud date: _____ Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.