

10-23

121R

To: 1 070868  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-171-20,415-00-00  
SE SW SW, SEC. 9, T 19 S, R 31 W/EK  
330 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422  
Operator: Abercrombie Drilling, Inc.  
Name & Address: 150 N. Main, Suite 801  
Wichita, KS 67202

Lease Name Ball Well # 1  
County Scott 152.26  
Well Total Depth 4685 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422  
Address 150 N. Main, Suite 801, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 23 Month: 10 Year: 19 90

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841  
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2974'  
Anhydrite 2255-73'

1st plug at 2290' with 50 sx cement, 2nd plug at 1600' with 80 sx cement,  
3rd plug at 330' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:45 p.m. Day: 23 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2290' with 50 sx cement,  
2nd plug at 1600' with 80 sx cement,  
3rd plug at 330' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.  
(If additional description is necessary, use BACK of this form.)

INVOICED (Do not observe this plugging.)

DATE 10-30-90

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 29782

10-23

EFFECTIVE DATE: 10-15-90

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas

NOTICE OF INTENTION TO DRILL 15-171-20, 415-00-00  
Must be approved by the K.C.C. five (5) days prior to commencing well

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Expected Spud Date 10 15 90  
month day year

SE SW SW Sec 9 Twp 19 S, Rg 31 East West

OPERATOR: License # 5422  
Name: Abercrombie Drilling, Inc.  
Address: 150 N. Main, Suite 301  
City/State/Zip: Wichita, KS 67202  
Contact Person: Jerry A. Langrehr  
Phone: (316) 262-1841

330 feet from South line of Section   
4290 feet from East line of Section   
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5422  
Name: Abercrombie Drilling, Inc.

County: Scott  
Lease Name: Ball Well #: 1  
Field Name: WC

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary   
... Casing ... Disposal  Wildcat ... Cable  
... Seismic; ... # of Holes

Is this a Prorated Field? yes  no   
Target Formation(s): LKC and Marmaton  
Nearest lease or unit boundary: 330'

If OKWD: old well information as follows:  
Operator: N/A  
Well Name: Wichita  
Comp. Date: OCT 9 1990 Old Total Depth

Ground Surface Elevation: 2975 est. feet MSL  
Domestic well within 330 feet: yes  no   
Municipal well within one mile: yes  no   
Depth to bottom of fresh water: 150'

Directional, Deviated or Horizontal wellbore? yes  no   
if yes, total depth location: N/A

Depth to bottom of usable water: 1550'  
Surface Pipe by Alternate: 1  2   
Length of Surface Pipe Planned to be set: 275'

Length of Conductor pipe required: N/A  
Projected Total Depth: 4650'  
Formation at Total Depth: Miss.

Water Source for Drilling Operations: well  farm pond  other   
DWR Permit #: will file  
Will Cores Be Taken?: yes  no   
if yes, proposed zone: N/A

Exp. 4/10/91

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher 10-11-90 Tony Martin  
SPUD DATE INIT. DG  
LENGTH SURFACE PLANNED 225'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 5/8" @ 313' CONDUCTOR  
ANHYDRITE T- 2255' B- 2273' ELEVATION 2374'  
TD 4685' FORMATION  
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
1 Anhydrite Base @ 2290 Ft. W/ 50 SX  
1/2 Base Anhyd. @ Ft. W/ SX  
2 1/2, 1/2 Plug @ 1600 Ft. W/ 80 SX  
3 Bottom Surface @ 330 Ft. W/ 40 SX  
4 40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRE/W 15 SX MOUSE HOLE W/ SX  
WATER WELL SX (Irr. Well) Fond Hauling  
TECHNICIAN DG DATE 10-11-90  
TYPE OF CEMENT 60/40 69% 4FC111SX  
STARTING TIME 2 PM (AM/PM) DATE 10-23-90  
COMPLETION TIME 5:45 (AM/PM) DATE 10-23-90  
CEMENT COMPANY B J Services