

To: 1 070656
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3857

Operator: Unico Inc.
Name & Address 165 South Union Blvd., Suite 602
Lakewood, CO 80228

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address Box E, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 5 Month: 4 Year: 19 89

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service

were: 4 1/2" at 2825' Perfs at 2768', 4 holes

1st plug pump 2 sx hulls and 20 sx cement at 2768',

2nd plug pump 80 sx cement at 1420',

3rd plug pump 40 sx cement at 270',

4th plug pump 10 sx cement at 40'. All through casing.

RECEIVED (phone) 316-675-8349
STATE CORPORATION COMMISSION

APR 13 1989
04-13-89

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 5 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx common cement at 2768',
Pump through casing:

2nd plug pumped 80 sx cement at 1420',

3rd plug pumped 40 sx cement at 270',

4th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Midwest Casing Pullers. Recovered 1452' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-20-89

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 24407
4-5