

1 060780

R (242) 00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,318

C NW NE SE, SEC. 3, T 19 S, R 31 W/EX

2310 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Janssen Well # 1

Operator: A. L. Abercrombie, Inc.

County Scott 156.31

Name &

Address 801 Union Center

Well Total Depth 4625 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 7:15 am Day: 23 Month: January Year: 19 86

Plugging proposal received from Wayne Shively

(company name) Abercrombie (phone) 316-262-1841

Anhydrite 2293-2308*

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2931

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 am Day: 23 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement, 2nd plug at 1350' with 80 sx

cement, 3rd plug at 370' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1986

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.)

! ~~NO~~ / did not observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE FEB 4 1986

INV. NO. 12266

1-23

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 1-14-86
month day year

API Number 15- 171-20,318-00-00

OPERATOR: License # 5393
Name A. L. Abercrombie, Inc.
Address 901 Union Center
City/State/Zip Wichita, KS 67202
Contact Person Jack L. Partridge
Phone 316-262-1841

Q. NW. SE. Sec. 31. Twp. 19. S. Rge. 31. E. East
(location) West
2310 Ft North from Southeast Corner of Section
990 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, KS

Nearest lease or unit boundary line 330 feet
County Scott
Lease Name Janssen Well#
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Snd Infield Mud Rotary
 Gas In Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 200 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 2000 / 1200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 325 feet
Conductor pipe if any required None feet
Ground surface elevation 2931 G.L. feet MSL.
This Authorization Expires 7-14-86
Approved By 1-14-86

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4600 feet
Projected Formation at TD Miss
Expected Producing Formations Miss

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 1-14-85 Signature of Operator or Agent Jack L. Partridge Title V.P. Abercrombie Drilling
Jack L. Partridge Form C-1 4/84

Move in 1-15-85 340' 0" / 8 7/8

PUSHER Wayne Shively

TD 4625 FORMATION Miss

SURFACE PIPE 8 7/8 @ 840

ANHYDRITE 2300 P ELEVATION 2931

STARTING TIME & DATE 2:11 PM 1-23-86

COMPLETION TIME & DATE 11:30 AM 1-23-86

1st PLUG @ 2500 FT. W/ 50 SX

2nd PLUG @ 1570 FT. W/ 80 SX

3rd PLUG @ 370 FT. W/ 50 SX

4th PLUG @ 40 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ SX

CEMENT COMPANY BT 340793 60/406

TECHNICIAN

1st ann w/ 50

2nd Chaps w/ 80

3rd 30' out w/ 50

4th 40-8 - 5BP-10 dbx

15' out

60/40 w/ 6 7/8

STATE OF KANSAS COMMISSION
OIL AND GAS
OBSERVATION DIVISION
Wichita, Kansas
VAN 27 1986