

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171 -20,242 -00-00
100' SW/C-
NW/4, Sec. 2, T 19 S, R 31 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Steinberg Twin Well # 1

Operator: A. L. Abercrombie, Inc.
Name & 801 Union Center
Address Wichita, KS 67202

County Scott

Well Total Depth 4500 feet 146.25

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor A. L. Abercrombie, Inc. License Number 5393

Address Rt. 1, Box 56, Great Bend, KS 67530

Company to plug at: Hour: 7:00 am Day: 17 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Kevin Wiley

(company name) A. L. Abercrombie, Inc. (phone) 316-793-8186

were: 5 1/2 set at 4498 Perfs at 4384-90 4396-4400 DV Tool at 1513'

Circulate cement to surface

Top plug pump 2 sx hulls, 30 sx cement, 20 sx gel, 50 sx cement, 5 sx gel and 1 sack hulls and pump an additional 125 sx cement.

Maximum pressure 100# and shut in pressure 0

Signed Steve Shumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:35 am Day: 17 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4498' Perfs at 4384-90 and 4396-4400

DV Tool at 1513' Circulate cement to surface Top plug pump 2 sx hulls, 30sx cement, 20 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls and pump an additional 125 sx cement.

Maximum pressure 100# and shut in pressure 0

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun Cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed Steve Shumant
(TECHNICIAN)

1030103
2-17