

1 060597

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,304-00-60

NE NW SW, SEC. 25, T 19 S, R 31 ~~W~~
2310 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Drew Well # 1

Operator: Abercrombie Drilling, Inc.

County Scott 152.26

Name:

Address 801 Union Center

Well Total Depth 4685 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 6:00 am Day: 25 Month: October Year: 19 85

Plugging proposal received from Tony Martin

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2944 GL Anhydrite 2257-74'

1st plug in the Arbuckle with 50 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug in the Cedar Hills with 50 sx cement

4th plug 30' below the base of the surface pipe with 50 sx cement
solid bridge - hulls - plug at 40' -- cement to surface

5th plug with 10 sx cement Plugging Proposal Received by Paul A. Luthi

7th plug to circulate rat hole with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00 am Day: 25 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2270' with 50 sx cement, 2nd plug at 1450' with 50 sx

cement, 3rd plug at 358' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

10-26-85
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

Observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE OCT 29 1985

INV. NO. 10761
10-25

FORM CP-2/3
Rev. 01-84