

1 060862

11 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,336-00-00
W/2 NW NE SEC. 22, T 19 S, R 31
4620 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422
Operator: Abercrombie Drilling Inc.
Name & Address 801 Union Center
Wichita, Ks 67202

Lease Name Stuckey C Well # 1
County Scott 152.10
Well Total Depth 4680 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address 801 Union Center, Wichita, Ks 67202

Company to plug at: Hour: 10:30 pm Day: 9 Month: July Year: 1986

Plugging proposal received from Harold Millie

(company name) Abercrombie (phone) (316)262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2954
Anhydrite 2283-2299'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyene with 80 sx cement

3rd plug at 30' below the base of the surface pipe with 50 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:00 am Day: 10 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement, 2nd plug at 1500' with 80 sx
cement, 3rd plug at 380' with 50 sx cement, 4th plug from 40' to surface with 10 sx
cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

JUL 18 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observed, observe this plugging.)

DATE 7-21-86

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 14402

7-10