

To: 1 051470  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-17 82 R  
API NUMBER 15-171-20,074-00-00  
C SE, SEC. 24, T 19 S, R 32 W/EX  
1320 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3857

Lease Name F.W. Yager Well # 1-24

Operator: Unico Inc./Inter Mountain Chemical  
Name: Inc.  
Address: P.O. Box 69  
Commerce City, CO 80022

County Scott 92.30  
Well Total Depth 2840 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 9 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service (phone) 316-675-8349

were: 5 1/2" at 2839' w/150 sx cement, PBDT 2799', Perfs at 2781-91'

RECEIVED  
KANSAS CONSERVATION COMMISSION  
SEP 19 1991  
09-19-91  
CONSERVATION  
WICHITA, KS

1st plug pump 2 sx hulls and 20 sx cement over perfs,

2nd plug pull to 1450' with 80 sx cement,

3rd plug pull to 300', circulate cement to surface.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 17 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement,

Spotted plugs through casing:

2nd plug at 1450' with 80 sx cement,

3rd plug circulated cement from 300' to 0'.

Remarks: Used common cement by Midwest. Recovered 1793' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did not) ~~authorize~~ **INVOICED** consent to this plugging.

Signed Richard W. Tracy (TECHNICIAN)

DATE 10-23-91

INV. NO. 33421