

Corrected Copy

Doc# 17, 216

070669

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
260 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,056-00-00

C. SW SE, SEC. 12, T 19 S, R 32 W/E

660 feet from S section line

1980 feet from E section line

Lease Name McCutchen A Well # 1

County Scott 131.79

Well Total Depth 4055 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 555

TECHNICIAN'S PLUGGING REPORT

Operator License # 3857

Operator: Unico Inc.

Name & Address 165 South Union Blvd., Suite 602,

Lakewood, CO 80228

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 2 Month: 5 Year: 19 89

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 4053' PBD 4012' Perfs at 2758-68' TOC 1639'

1st plug pump 2 sx hulls and 20 sx cement,

2nd plug pump 80 sx cement at 1340',

3rd plug pump 40 sx cement at 570',

4th plug pump 10 sx cement at 0-40'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 5 p.m. Day: 2 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement,

2nd plug pumped through casing 80 sx cement at 1340',

3rd plug pumped 40 sx cement at 570',

4th plug pumped 10 sx cement at 40'.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

MAY 9 1989

05-09-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling, Recovered 1340' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOLVED

Observe this plugging.

DATE 5-10-89

INV. NO. 24745

5-2

Signed Dan Jordan
(TECHNICIAN)