

15-171-20422-00-01

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: ~~15-171-20422-00-00~~  
Spot: NESW Sec/Twnshp/Rge: 9-19S-33W  
4620 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: MILLER Well Number: 1-9  
County: SCOTT Total Vertical Depth: 4755 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Production Casing Size: 4.5 feet: 4750 WITH 200 SX CMT  
Surface Casing Size: 8.625 feet: 351 WITH 225 SX CMT

\$154.54

Well Type: EOR UIC Docket No: E27409.1 Date/Time to Plug: 02/19/2003 11:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KEN RUPP Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: PUMP 400# HULLS & 50 SX CMT. GEL SPACER TO 2400'. CMT FROM 2400' TO 0'. TEST 8 5/8 X 4 1/2 ANNULUS. 50 SX CMT IF NEEDED.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/19/2003 12:45 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4600'. PERFS AT 4371-75'. CIBP @ 4600'. PERFS BELOW 4650-54'. DV @ 2230' WITH 450 SX CMT. PUMPED DOWN 4 1/2" CASING 50 SX CMT WITH 400# HULLS 8 SX GEL SPACER TO 2400'. PUMPED 130 SX CMT FROM 2400' TO 0'. MAXIMUM PRESSURE 1200#. SHUT IN PRESSURE 1200#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 50 SX CMT. CIRCULATED UP BACKSIDE OF 8 5/8".

RECEIVED  
FEB 28 2003  
02-28-03  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
FEB 26 2003  
KCC Dodge City

Signed

*Kevin D Strube*

(TECHNICIAN)

INVOICED  
DATE 2-28-03  
WV. NO. 2003061251

Form CP-25