

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20312-00-01
Spot: CN2NW Sec/Twnshp/Rge: 9-19S-33W
4620 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: MILLER Well Number: 2-9
County: SCOTT Total Vertical Depth: 4735 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Production Casing Size: 4.5 feet: 4717 WITH 325 SX CMT
Surface Casing Size: 8.625 feet: 432 WITH 300 SX CMT

8153.89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2003 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEN RUPP Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: PUMP 400# HULLS & 50 SX CMT. GEL SPACER TO 2400'. CMT FROM 2400' TO 0'. TEST 8 5/8 X 4 1/2 ANNULUS. 50 SX CMT IF NEEDED.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/19/2003 11:00 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4376'. PERFS AT 4362-65. CIBP @ 4376'. PERFS BELOW 4382-87 & 4598-4602'. DV TOOL @ 2188' WITH 400 SX CMT. PUMPED DOWN 4 1/2" CASING 50 SX CMT WITH 400# HULLS. 8 SX GEL SPACER TO 2400'. PUMPED 130 SX CMT. MAXIMUM PRESSURE 1300#. SHUT IN PRESSURE 1300#. PUMPED DOWN 8 5/8" X 4 1/2' ANNULUS 5 SX CMT. PRESSURED UP TO 500# & SHUT IN.


RECEIVED

FEB 28 2003
02-28-03
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin Strube

(TECHNICIAN)

INVOICED
DATE: 2-28-03
NOV. NO. 2003061251

Form 01-03