

To: 1 030694
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,330-00-00
SW SE, SEC. 7, T 19 S, R 33 W
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210
Operator: Lebsack Oil Production, Inc.
Name
Address P. O. Box 489
Hays, KS 67601

Lease Name Hutchins Well # 1-7
County Scott 154.38
Well Total Depth 4750 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 422

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 7:45 am Day: 20 Month: April Year: 19 86

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2993 Anhydrite 2238-2255'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 50 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 pm Day: 20 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement; 2nd plug at 1338' with 50 sx cement, 3rd plug at 455' with 50 sx cement, 4th plug from 40' to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1986

CONSERVATION DIVISION
Wichita, Kansas 04-2886

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (If necessary) observe this plugging.

DATE APR 29 1986

Signed Steve Summit
(TECHNICIAN)

INV. NO. 13588

4-20 MAY 28 1986

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date April 15 1986 month day year

API Number 15- 171-20,330-995 SW SE Sec. 7 Twp. 19S S, Rg. 33W 660' Ft. from South Line of Section 1980' Ft. from East Line of Section

OPERATOR: License # 5210 Name Lebsack Oil Production Inc. Address Box 489 Hays, Kansas 67601 Contact Person Wayne Lebsack Phone 316-938-2396

Nearest lease or unit boundary line 660' feet County Scott Lease Name Hutchina Well # 2-7

CONTRACTOR: License # 5422 Name Abercrombie Drilling, Inc. City/State 801 Union Center, Wichita, Ks.

Ground surface elevation 2993 GR. feet MSL Domestic well within 330 feet: -- yes X no Municipal well within one mile: -- yes X no

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary X Gas Inj X Pool Ext. Air Rotary OWWO Expl Wildcat Cable

Depth to bottom of fresh water 200' Depth to bottom of usable water 1150' 1300' Surface pipe by Alternate: 1-2 X

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe planned to be set 360' Conductor pipe required Projected Total Depth 4800' feet Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 4/5/86 Signature of Operator or Agent Rex Urtis Title Agent

For KCC Use: Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 400 feet per Alt. This Authorization Expires 10-2-86 Approved By 4-7-86

move in 4-10-86 set 8 3/8 400' + 200'

SW SE Sec. 7 Twp. 19S S, Rg. 33W

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2190' Bascony feet depth with 50/sx sxs of 60/40 poz. 2nd plug @ 1200' Bay-Chief feet depth with 50/sx sxs of 2nd plug @ 458' Bascony 3rd depth with 50/sx sxs of 4th plug @ 10' salt bridge feet depth with 10/sx sxs of 5th plug @ feet depth with sxs of (2) Rathole with 15/sx 60/40 sxs 6% gel (b) Mousehole with sxs

Table with columns: PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @, 2nd PLUG @, 3rd PLUG @, 4th PLUG @, RAT HOLE CIRCULATED W/, MOUSE HOLE CIRCULATED W/, WATER WELL PLUGGED W/, CEMENT COMPANY, TECHNICIAN

STATE CORPORATION COMMISSION APR 28 1986 CONSERVATION DIVISION Wichita Kansas