


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Greeley County, Sec. 26 Twp. 20 Rge. 4 (W)

Location as "NE/CNW/SW" or footage from lines Ctr. NW SE
Lease Owner Champlin Oil & Refining Co.
Lease Name Charles A. Greamba Well No. 1
Office Address P.O. Box 308, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 22 1962
Application for plugging filed January 3 1963
Application for plugging approved January 4 1963
Plugging commenced January 8 1963
Plugging completed January 22 1963
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2875 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7 5/8" OD	212'	None
				4 1/2" OD	2870	2249'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from Total Depth to 2750'
and dumped 3 sacks of cement on top. Filled hole
with heavy mud from top of cement to 200' and set
10' rock bridge to 190' and dumped in 30 sacks of
cement then filled hole with mud to 50' and set 10'
rock bridge and dumped in 15 sacks of cement filling
hole to bottom of cellar.

JAN 25 1963

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Central Pipe Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. W. Meyers (employee of owner) or ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Meyers
P.O. Box 308, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 63

My commission expires 5-22-66 Notary Public.

15-071-19003-00-00

LEASE: CHARLES A. GREAMBA #1
OWNER: CHAMPLIN OIL & REFINING CO.
CONTRACTOR: EARL F. WAKEFIELD
COMM: 11-12-62 COMP: 11-18-62

LOCATION: C NW SE
SECTION 26-20S-41
GREELEY COUNTY, KANSAS
CASING: 7 5/8" Set @ 212'
4 1/2" Set @ 2868'

Surface Soil	30
Sand & Shale	80
Shale	175
Blue Shale	214
Shale & Shells	790
Shale & Shells	1310
Shale, Red Bed & Shells	1585
Shale & Shells	1700
Anhydrite & Shale	1840
Shale & Shells	2385
Shale, Red Anhydrite	2398
Shale & Anhydrite	2450
Red Bed, Shale & Lime	2633
Red Bed, Shale, Lime Pyrite	2762
Lime, Shale, Pyrite	2836
Lime & Shale	2875
T.D.	2875

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the CHARLES A. GREAMBA #1 well, located C-NW-SE, SECTION 26-20S-41, GREELEY COUNTY, KANSAS.

EARL F. WAKEFIELD

By *Earl F. Wakefield*

Subscribed and sworn before me this 3rd day of December, 1962

My Commission expires: *Wanda M. Riley*
NOTARY

January 25, 1965