

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER <sup>15</sup> 071-20,429-00-00

LEASE NAME BLM

WELL NUMBER 1

4125 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 23 TWP. 20S RGE. 43 (R) or (W)

COUNTY Greeley

Date Well Completed 1-8-87

Plugging Commenced 3-13-97

Plugging Completed 3-13-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Lee Banks d/b/a Banks Oil Co.

ADDRESS 200 W. Douglas, Suite 550, Wichita, Ks 67202

PHONE# (316) 267-0783 OPERATORS LICENSE NO. 05152

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 10, 1997 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5082 Bottom 5094 T.D. 5315

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	358	8-5/8	358	0
		0	5314	4-1/2"	5314	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP at 5150'. 25 sx cement 65/35 Posmix, 6% gel and 2 sack cottonseed hulls 5150' to 4820'. Mix and pump 21 sx gel 4820' to 1800'. Pull tbg to 1800'. Pump 105 sx cement, circ. to surface. Pull tbg. Top off csg. with 10 sx cement. Pressure 8-5/8" - 4-1/2" annulus to 300 psi. P&A complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Well Service License No. 54

Address P.O. Box 384, Ness City, Ks. 67560-0384

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Banks Oil Co.

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Lee Banks (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lee Banks

(Address) 200 W. Douglas, Suite 550, Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 17th day of March, 1997



Darlene J. May  
Notary Public Darlene J. May