

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-071-20481-00-00

LEASE NAME Lemon

WELL NUMBER #1

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 32 TWP. 20S RGE. 40 (E) or (W)

COUNTY Greeley

Date Well Completed D & A

Plugging Commenced 12-10-89

Plugging Completed 12-10-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bartling Oil Co.

ADDRESS 8550 Katy Freeway, Suite 128, Houston, TX

PHONE# (713) 465-1093 OPERATORS LICENSE NO. 77024 7271

Character of Well Plugged

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas - Steve Durant 12-10-89

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation U Winfield Depth to Top 2794 Bottom 2820 T.D. 2910

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota	Water	900	1050	8 5/8	315	Cement to surface
Cheyenne	Water	1200	1400			
Chase	Gas	2800	2910			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Howco 60/40 Poz mix, 6% gel, 1/2# flocele; 1st plug @ 2400' w/ 50sx, 2nd @ 1490' w/ 80sx, 3rd @ 810' w/ 40 sx, 4th @ 330' w/ 40 sx, 5th @ 40' -- 0 w/ 10sx, rathole 15 sx, mousehole 10 sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. N/A


Address Box 1303, Lamar, CO 81052

STATE OF Kansas COUNTY OF Seward, ss.

Terry W. Maxwell, Maxwell Consulting (Employee of Operator) or (Operator) of above-described well, being first-duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W Maxwell

(Address) P. O. Box 800, Liberal, KS



FEB 19 1990

SUBSCRIBED AND SWORN TO Before me this 16 day of February, 1990

[Signature]  
 Notary Public

My Commission Expires: 12-13-92

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bartling Oil Co.