

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas 67202
39 W
NORTH

15-071-00015-00-00
WELL PLUGGING RECORD

GREELEY COUNTY, KANSAS County. Sec. 8 Twp. 20S Rge. 39W (E) W (W)

Location as "NE/CNW%SW%" or footage from lines C SE SE Sec. 8

Lease Owner Van-Grisso Oil Company et al

Lease Name Marvin Watson #1 Well No. 1

Office Address 1012 City National Building, Oklahoma City 2, Okla

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed September 24 for testing (rotation 8/23/56) 19 56

Application for plugging filed October 23 19 56

Application for plugging approved October 24 19 56


Plugging commenced November 17 19 56

Plugging completed November 19 19 56

Reason for abandonment of well or producing formation non-productive - dry hole

If a producing well is abandoned, date of last production dry hole 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege, Hoisington, Kansas

Producing formation none Depth to top Bottom Total Depth of Well 5388 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Ogallala water sds	water	various	240'	13-3/4"	265'	none
				8-5/8"	2418'	1217'
				5-1/2"	3111	1988'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Plug of 10 sx, regular cement at 2420'
" " of 30 " " " " 265'
" " of 15 " " " " surface

RECEIVED
STATE CORPORATION COMMISSION
NOVEMBER 11-30-56

Name of Plugging Contractor R. D. Casing Pulling Service, (License No. 236)
Address Ellinwood, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma ss.
Don L. Hyatt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don L. Hyatt

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 56


January 7, 1957

My commission expires

Mary Pylant
Notary Public.

Driller's log of well is attached hereto.

PLUGGING
FILE SEC 8 T 20 R 39W
BOOK PAGE 110 LINE 6



15-071-00015-00-00

NO. 1 WATSON

WELL LOG

Location: SE SE 8-208-39W
Greeley County, Kansas

Commenced: July 7, 1956

Operator: Van-Grisee Oil Company
1012 City National Bldg, Oklahoma City, Okla.

Completion: August 23, 1956

Contractor: Neuman-Rinehart Drig. Company
518 Petroleum Bldg, Wichita, Kansas

Elevation: 3529 KB

Productions:

Casing Records: 13 3/4" @ 265' w/265 sacks cement
8 5/8" @ 2428' w/200 sacks cement
5 1/2" @ 3120' w/150 sacks cement

..L O G . . .

Clay-sand	240
Shale	655
Shale-sand streaks	1060
Shale	1280
Shale-streaks Anhydrite	1500
Shale-Red bed	1708
Shale-lime	1836
Salt	1862
Salt-shale	2067
Salt	2097
Shale-Red bed	2318
Shale-Red bed-salt	2413
Anhydrite	2430
Shale	2775
Shale-sand	2812
Sand	2960
Sand-shale	3155
Lime-shale	3270
Shale	3296
Lime	3393
Shale-lime	3565
Lime-shale	3880
Lime	3922
Chalky lime-shale	3980
Lime-shale	4058
Lime	4141
Lime-shale	4271
Lime	4342
Sand-lime	4420
Lime	4535
Lime-sand	4574
Lime-shale	4691
Lime	4742
Lime-shale	4917
Lime	4943
Lime-shale	4995
Lime	5026
Lime-shale	5125
Lime-sand	5179
Lime-shale	5194
Lime-sand	5216
Lime	5388 R.T.D.

RECEIVED
STATE DEPARTMENT OF GEOLOGY

Sample Tops:

Lansing 4241' (-712)
Marathon 4445' (-916)
Mississippi 5178' (-1659)

The undersigned, NEUMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

NEUMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this 29th day of August, 1956.

James L. Lewis
Notary Public

My Commission Expires: November 5, 1958

PLUGGING
FILE SEC 8, T. 20 R. 39W
BOOK PAGE 110 LINE 6