

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

REGISTRATION RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20638-02-01

LEASE NAME Kuttler

WELL NUMBER 1-6

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 6 TWP. 20 RGE. 39 (E) or (W)

COUNTY Greeley

Date Well Completed 10-4-95

Plugging Commenced 6-2-97

Plugging Completed 6-2-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Horseshoe Operating, Inc.

ADDRESS 500 W. Texas, Suite 1190 Midland, Tx 79701

PHONE# (915) 683-1448 OPERATORS LICENSE NO. 04894

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-3-97 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?         

Producing Formation Winfield Depth to Top 2818 Bottom 2836 T.D. 2858

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Winfield	Gas & SW	0	355	8-5/8	355	0
2818-2836		0	2857	4-1/2	2857	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Pump down casing 100# cottonseed hulls w/ 150 sxs +- 60/40 poz mix with 6% gel.  
Pressure to 750#, SI 24 hrs. and cut off csq 3' below ground level.

Name of Plugging Contractor Allied Cementing License No.         

Address Box 31 Russel, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Horseshoe Operating, Inc.

STATE OF Texas COUNTY OF Midland, ss.


S. L. Burns (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) S. L. Burns

(Address) 500 W. Texas, Suite 1190

SUBSCRIBED AND SWORN TO before me this 18 day of June, 1997

Debbie Hanson  
Notary Public



Expires: 8-9-97

# MERCURY WIRELINE

CHEYENNE WELLS CO  
719-767-5522

## GAMMA RAY/CCL/BOND LOG

FILING NO.		COMPANY HORSESHOE OPERATING CO.					
		WELL KUTLER NO. 1-6		15-071-20638-0000			
		FIELD					
		COUNTY GREELEY		STATE KS			
		LOCATION W/2 NW NW		OTHER SERVICE			
		SEC 6 TWP 20S RGE 39W					
PERMANENT DATUM GL		ELEV 3550		ELEVATIONS		KB 3556	
LOG MEASURED FROM KB .6		FT. ABOVE PERMANENT DATUM		DF		GL 3550	
DRILLING MEASURED FROM KB							
DATE	9/28/95						
RUN NO.	ONE						
TYPE LOG	GRCBLCCL						
DEPTH DRILLER	2858						
DEPTH LOGGER	2814						
BOTTOM LOGGED INT.	2813						
TOP LOGGED INT.	200						
TYPE FLUID IN HOLE	WATER						
DENSITY	1.00						
FLUID LEVEL	FULL						
MAX. HOLE TEMP.	110						
TRUCK NO.	TR-1						
LOCATION	CW						
RECORDED BY	HENDERSON						
WITNESSED BY	HIGGINBOTTOM						
BORE HOLE RECORD				CASING RECORD			
RUN	BIT	FROM	TO	SIZE	WT.	FROM	TO
ONE	12 1/4	00	355	8 5/8	24	00	355
TWO	7 7/8	00	2857	4 1/2	10.5	00	2858

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 03 1997

CONSERVATION DIVISION  
WICHITA, KS

