

15-171-20071-00-00


FORM CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Scott County, Sec. 20 Twp. 17S Rge. 31W (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines C SE SW  
Lease Owner Okmar Oil Co.  
Lease Name Boyer Well No. 1  
Office Address 1130 Vickers-KSB&T Bldg., Wichita, KS 67202  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed November 5 1974  
Application for plugging filed November 5 1974  
Application for plugging approved November 5 1974  
Plugging commenced November 5 1974  
Plugging completed November 5 1974  
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4175' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	-0-

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1974  
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet for each plug set.

Plugged Hole: Filled Hole w/Mud & Set  
Plug @ 975 w/70 sx. cmt. 50-50 pozmix & 6% gel.  
Set Plug @ 310' w/20 sx. cmt.  
Set Plug @ 40' w/1/2 sk. hulls & 10 sx. cmt.

Name of Plugging Contractor RED TIGER DRILLING CO.  
Address 1720 Wichita Plaza, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick ss.  
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens  
1720 Wichita Plaza, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 1974

My commission expires December 28, 1977

(Signature) D'Ann Drennan  
Notary Public.



15-171-20071-00-00

DRILLERS LOG

No. 1 Boyer

CASING RECORD:

8-5/8" @ 300'  
w/200 ss. cnt.

TOTAL DEPTH: 4175'

COMPANY:

Pharr Oil Co.

CONTRACTOR:

Red Tiger Drilling Co.

COMMENCED:

October 26, 1974

COMPLETED:

November 5, 1974

DESCRIPTION:

C SE SW  
20-17S-31W  
Scott County,  
Kansas

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	220	
Shale	220	1782	
Bl. Anhydrite	1782	1818	
Shale & Shells	1818	1886	
Sand	1886	2060	
Shale	2060	2086	
Redbed	2086	2250	
Anhydrite Stringer	2250	2267	
Redbed	2267	2293	
Anhydrite	2293	2312	
Redbed & Shale	2312	2533	
Shale & Lime	2533	2826	
Lime	2826	2969	
Shale & Lime	2969	3780	
Lime	3780	4175	

RECEIVED  
STATE REGISTRATION COMMISSION  
JAN 6 1974

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens  
Linda H. Dickens

Subscribed and sworn to before me this 13th day of November, 1974.

D. Ann Drennan  
Notary Public

My Commission Expires:

December 28, 1977

