

15-171-30004-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Scott County, Sec. 19 Twp. 17 Rge. 31w (E) (W)

Location as "NE/CNWKSWK" or footage from lines C se ne

Lease Owner Cleary Petroleum Inc.

Lease Name See Well No. 3

Office Address 310 Kermac Bldg. Oklahoma City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 19

Application for plugging filed 11 - 16 19 65

Application for plugging approved 11 - 17 19 65


Plugging commenced 11 - 27 19 65

Plugging completed 11 - 30 19 65

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	296	0
				5 1/2	4039	3025'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mix 20 sacks cement to plug off bottom perforrations at 4020 feet. Stop plug at 3800 feet, Shoot pipe loose at 3025 feet and pull to 650 feet, Circulate mud at 650 feet, Lay down two joints and spot 20 sacks cement at 600 feet, Lay pipe down to 300 feet and spot 20 sacks cement at 300 feet, Finish laying down 5 1/2" casing and put 10 sacks cement at 35 feet to base of cellar. Cut 8 5/8 casing off 3 feet below ground level and weld cap on same.

DEC - 7 1965

Name of Plugging Contractor Sargent's Casing pulling Service
Address Box 506 Liberal, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

W. W. Jones

(employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Jones

310 Kermac Building, Oklahoma City

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 65

My commission expires March 1, 1967

[Signature] Notary Public.

LEASE: SEE NO. 3	LOCATION: SE NE
OWNER: CLEARY PETROLEUM, INC.	SECTION 19-17S-31W
CONT: EARL F. WAKEFIELD	SCOTT COUNTY, KANSAS
COMM: 10-16-65	CASING: 8 5/8" SET @ 296'
COMP: 11-1-65	5 1/2" SET @ 4093'

Surface Soil	40
Sand & Clay	230
Blue Shale	296
Shells	1300
Shale	1778
Anhydrite	1820
Red Bed & Shale	2240
Shale & Lime	2395
Shale & Shells	2730
Shale With Lime	2864
Shale & Lime	3199
Lime	4225
R.T.D.	4225

RECEIVED
STATE CORPORATION COMMISSION
DEC - 7 1965
CONSERVATION DIVISION
TOPEKA, KANSAS

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, FRED S. BARKER, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE SEE NO. 3, LOCATED IN THE SE NE OF SECTION 19-17S-31W, SCOTT COUNTY, KANSAS.

EARL F. WAKEFIELD

BY Fred S. Barker

SUBSCRIBED AND SWORN TO BEFORE ME THIS 9TH DAY OF NOVEMBER, 1965.

MY COMMISSION EXPIRES:
JANUARY 25, 1969

Wanda W. Riley
WANDA W. RILEY NOTARY PUBLIC