


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

15-17-00089-00-00

NORTH



Locate well correctly on above  
Section Plat

Scott County. Sec. 19 Twp. 17 Rge. 31 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NW  
Lease Owner Imperial Drilling Company, Inc.  
Lease Name Lester See Well No. 1  
Office Address 903 Union Nat'l Bank Bldg., Wichita 2, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date application completed September 27 19 52  
Application for plugging filed December 31 19 52  
Application for plugging approved January 2 19 53  
Plugging commenced January 5 19 53  
Plugging completed January 5 19 53  
Reason for abandonment of well or producing formation oil in commercial quantities not found  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4685 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4685	1720

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 4375'.  
Dumped 5 sax of cement at 4375' with dump  
bailer. Top of cement 4340', filled hole  
with mud to 300'. Set rock bridge, dumped  
20 sax of cement. Top of cement 240',  
filled hole with mud to 35'. Set rock  
bridge, dumped 10 sax of cement for cap.

01-23-53

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company,  
Address P.O. Box 711, Great Bend, Kansas


STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL DRILLING COMPANY, INC.

(Signature) By: Raymond L. Bacon Vice-Pres.  
903 Union Nat'l. Bk. Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of January, 19 53

My commission expires January 4, 1954 Raymond L. Bacon Notary Public.

24-2675-S 2-52-20M



15-171-20089-00-00

DRILLERS LOG

Imperial Drilling Company, Inc.  
903 Union National Bank Building  
Wichita 2, Kansas

#1 See  
SW NE NW Sec. 19-17S-31W  
Scott County, Kansas

Total Depth: 4685'

Elevation: 2969' K.B.

Commenced: 9-2-52 Completed: 9-27-52 Production: Oil

Contractor: Imperial Drilling Company, Inc.  
903 Union National Bank Building  
Wichita, Kansas

Casing Record: Set 296' of 8 5/8" w/225 sacks cement.  
Set 4685' of 5 1/2" w/250 sacks cement.

Figures indicate bottom of formations:

Surface Clay & Sand	175'		
Sand & Shells	295'		
Shale & Shells	385'		
Sand & Shale	850'		
Shale & Shells	1085'		
Sand & Shale	1220'		
Shale & Shells	1500'		
Sand & Shale	1550'		
Red Rock, Shale & Shells	1745'		
Shale & Shells	1788'		
Anhydrite	1832'		
Shale & Shells	2450'		
Shale & Lime	2590'		
Shale & Brown Lime	2735'		
Shale & Lime	3565'		
Lime, Shale & Purite Streaks	3640'		
Lime & Shale	3855'		
Lime	3863'		
Lime & Shale	3903'		
Lime	4433'		
Lime Cherty	4485'		
Lime	4570'		
Mississippi	4574'		
Lime	4685'		
Total Depth (Rotary)	4685'		

		<u>TOPS</u>	
Elevation	2969'	K.B.	
Herrington	2740'	(7 229)	
Heobner	3078'	- 929	
Lansing	3900'	- 931	
Marmaton	4321'	-1352	
Mississippi	4584'	(-1615)	
Total Depth	4685'	-1716	

RECORDED & INDEXED  
JAN 21 1953  
DIVISION  
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL DRILLING COMPANY, INC.

By: Raymond L. Bacon  
Vice-President

Subscribed and sworn to before me this 30th day of September, 1952.

My Commission Expires:

Jan 1, 1954

Rayquinta Antle  
Notary Public

**PLUGGING**  
FILE SEC 19 T 17 S 31W  
BOOK PAGE 69 LINE 42