


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-171-20022-00-00 Form CP-4
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

County. Sec. 18 Twp. 17S Rge. (E) 31 (W)
Location as "NE/CNWSW" or footage from lines C SE SW
Lease Owner Irvin Kornfeld
Lease Name Brookover Well No. 1
Office Address 1007 Denver U.S. Natl Center, Denver, Colo
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-31 19 69
Application for plugging filed 5-31 19 69
Application for plugging approved 5-31 19 69
Plugging commenced 5-31 19 69
Plugging completed 5-31 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4635 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	290'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 100 sacks cement @ 800'
Plugged with 35 sacks cement @ 300'
Bridged with 1/2 sack hulls Plug @ 40' 10 sacks

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1969
CONSERVATION DIVISION
Wichita, Kansas
06-06-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address) _____

SUBSCRIBED AND SWORN TO before me this 5th day of June, 1969

My commission expires April 1, 1971

Ulanda Nichols
Notary Public.

15-171-20022-00-00

DRILLER'S LOG

COMPANY
CONTRACTOR
FARM
LOCATION

Irvin Kornfeld
LEBEN DRILLING, INC.
BROOKOVER #1
C SE SW SECTION 18-17S-31W
SCOTT COUNTY, KANSAS
5-20-69
5-31-69

COMMENCED
COMPLETED

0	40	Surface Soil, Clay, Shale
40	125	Clay
125	195	Sand
195	294	Shale, Blue Shale
294	1915	Shale, Sand
1915	2055	Shale
2055	2070	Anhydrite
2070	2475	Shale with Lime Streaks
2475	3775	Lime, Shale
3775	4635	Lime
	<u>4635</u>	<u>RTD - D. & A.</u>

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1969
CONSERVATION DIVISION
Wichita, Kansas

8 5/8" 20# new surface casing set @ 290' cemented with 235 sacks
Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
a true and correct copy of the log of the Brookover #1 Well, located
C SE SW of Section 18, Township 17 South, Range 31 West, Scott
County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
and for Barton County, Kansas, this 5th day of June, 1969.

Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1971