


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

15-171-20029-00-00 Form CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Scott County, Sec 2 Twp. 17 Rge 31 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines C SW SW
Lease Owner Yucca Petroleum Co.
Lease Name Huseman Well No. 1
Office Address Box 2585, Amarillo, Texas 79100
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-17-1970
Application for plugging filed 7-17-1970
Application for plugging approved 7-17-1970
Plugging commenced 7-17-1970
Plugging completed 7-17-1970
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	345'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug was set at 1196' with 70 sacks cement
2nd Plug was set at 312' with 20 sacks cement
3rd Plug was set at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (owner/contractor) of the above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

Subscribed and Sworn to before me this 18th day of July, 1970

My commission expires September 19, 1970
Joseph A. Hess Notary Public



L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

15-171-20029-00-60

Company Yucca Petroleum Co.
Box 2585
Amarillo, Texas 79100

Sec. 2 Twp. 17 Rng. 31

Farm Huseman No. 1

Location C SW SW

Total Depth 4794'

County Scott

Comm. 7-8-70 Comp. 7-17-70

Elevation: 2921' K. B.

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas 67671

2918' D. F.

Casing Record

Cement Record

2916' G. R.

345' - 8 5/8"

225 sacks cement

Production:

D & A

Figures Indicate Bottom of Formations

0'	140'	Top Soil & Clay
140'	200'	Sand
200'	356'	Shale
356'	1075'	Shale
1075'	1400'	Shale
1400'	1548'	Shale & Sand
1540'	1785'	Shale & Shells
1785'	1821'	Anhydrite
1821'	1845'	Shale, Shells & Red Bed
1845'	2308'	Shale & Sand
2308'	2328'	Anhydrite
2328'	2635'	Shale
2635'	2835'	Shale & Lime
2835'	3019'	Shale & Lime
3019'	3175'	Lime & Shale
3175'	3325'	Lime & Shale
3325'	3455'	Lime & Shale
3455'	3590'	Lime & Shale
3590'	3760'	Lime & Shale
3760'	3935'	Lime & Shale
3935'	4055'	Lime
4055'	4155'	Lime
4155'	4255'	Lime
4255'	4335'	Lime
4335'	4410'	Lime
4410'	4480'	Lime
4480'	4533'	Lime
4533'	4604'	Lime
4604'	4659'	Lime
4659'	4706'	Lime
4706'	4765'	Lime
4765'	4794'	Lime
4794'	T.D.	


RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Huseman #1.

Leo F. Dreiling
LEO F. DREILING

and sworn to before me this 18th day of July, 1970.



Joseph A. Hess
JOSEPH A. HESS NOTARY PUBLIC

Commission expires: September 19, 1970