



15-171-20052-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1970
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herb Morrell of Earl F. Wakefield, Inc., has this
date requested permission to plug the following described well:

Mr. Morrell guarantees payment of the plugging fee.

Operator's full Name: Marsh Oil Associates c/o Davies & Fitzgerald,

Complete Address: 1303 Phil tower Building, Tulsa, Oklahoma.

Lease Name: H. G. Witham Well No. 1

Location: 1320' FNL : 1320' FFL NE/4 ^{C NE/4} Sec. 29 Twp. 19 Rge. (E)(W) 31

County: Scott Total Depth 2850' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morrell was instructed to plug the well as follows:

357'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 950' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 370' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

M. L. DeHale
Conservation Division Agent