



15-171-20034-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Freeman of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc., and Beacon Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Mueller Well No. 1

Location: CNE-NW Sec. 26 Twp. 19 Rge. (E)(W) 31

County: Scott Total Depth 4800' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

450'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 110 Cu. Ft.
cement thru DP from 1200'. Pull DP to 475' and displace 30 Cu. Ft cement
thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

Very truly yours,

W. L. Fickel
Conservation Division Agent