

State of Kansas



15-171-20071-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1974

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Boyer Well No. 1

Location: CSE-SW Sec. 20 Twp. 17 Rge. (E)(W) 31

County: Scott Total Depth 4175' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

300'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 3/4 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols

Conservation Division Agent