



15-171-30004-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargent's Casings Pulling has this

date requested permission to plug the following described well:  
Cleary Petr. Inc.

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum, Incorporated,

Complete Address: 310 Kermac Building, Oklahoma City, Oklahoma.

Lease Name: See Well No. 3

Location: CSE-NE Sec. 19 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 4225 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

296'--8 5/8" Surface pipe, cement circulated.  
4039'--5 1/2" Production casing cemented with unknown amount. Per-  
forations from 4020' to 4025'.

Squceze bottom of hole with 20 Sx. cement. Pull 5 1/2" to 600'  
and circulate heavy gel mud. Pull 5 1/2" to 540' and displace  
20 Sx. cement thru 5 1/2". Pull 5 1/2" to 300' and displace 20 Sx.  
cement thru 5 1/2" pipe, set bridge @ 55' and 10 Sx. cement  
to bottom of well.

DEC - 3 1965

Very truly yours,

CONSERVATION DIVISION  
Wichita, Kansas

H. D. Nichols  
Conservation Division Agent