

State of Kansas



15-171-20022-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 2 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Executive Petroleum Co. & Petroleum, Incorporated,

Complete Address: 1007 Denver, US National Center, Denver, Colorado.

Lease Name: Brookover Well No. 1

Location: CSE-SW Sec. 18 Twp. 17 Rge. (E)(W) 31

County: Scott Total Depth 4635' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

290'--8 5/8" Surface casing, cement circulated with 235 Sx.
Top of Dakota section @ 550'.

Circulate hole with heavy mud. Pull DP to 800' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 35 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent