



15-171-00076-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company, Incorporated.

Complete Address: 301 South Broadway, Wichita, Kansas.

Lease Name: Brookover Well No. 1

Location: CSW-SE Sec. 18 Twp. 17 Rge. (E)(W) 31

County: Scott Total Depth 4777' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

276'--8 5/8" Surface casing, cement circulated.
4255'--5 1/2" Production casing cemented on bottom with 95 Sx. Top perforation @ 4030'. Temperature survey @ 3768'. Hole squeezed @ 1650' with 200 Sx. cement.
Push plug to 4000', build sand bridge and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 30 sacks gel and 130 Sx. cement staged.

Very truly yours,

Conservation Division Agent