



15-171-20049-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 5 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSBOT Building, Wichita, Kansas.

Lease Name: Rodenberg Well No. 1

Location: CSW-SW Sec. 17 Twp. 17 Rge. (E)(W)31

County: Scott Total Depth 4038 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

338'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 365' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent