

State of Kansas



15-171-00064-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

STATE CORPORATION COMMISSION

NOV 9 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Csg. Pulling Co., has this

date requested permission to plug the following described well:
R. W. Rine Drilling Co.

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: R. W. Rine Drilling Company,

Complete Address: 420 Union Center, Wichita, Kansas.

Lease Name: Rodenberg Well No. 1

Location: CNW-NW Sec. 16 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 4647 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

284'--8 5/8" Surface pipe, cement circulated. 4647' 5 1/2" Production casing cemented with 150 Sx. Well plugged back to 4613'. Top perforations @ 4567'.

Sand well back to 4560 and set 5 Sx. cement with dump bailer. Pull 5 1/2" to 660' and circulate heavy gel mud. and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 260' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 30' and 10 Sx. cement to bottom of cellar.

Very truly yours,

J. P. Roberts
Conservation Division Agent