

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

YOUR COPY FORM CP-1
Rev 10/3/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-203-20,099-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Falcon Exploration, Inc. KCC LICENSE # 5316
ADDRESS 155 N. Market, Suite 1010 (owner/company name) CITY Wichita (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1378

LEASE Kalbach WELL# 1 SEC. 16 T. 17S R. 37 (East/West)

SE - SE - SPOT LOCATION/QQQQ COUNTY Wichita

550' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

550' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ___ GAS WELL ___ D&A X SWD/ENHR WELL ___ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 343' CEMENTED WITH 60-40 posmix - 225 sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3299'-3304' T.D. 5120' PBDT _____ ANHYDRITE DEPTH 2459'-2480'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2500' w/50 sx; 2nd plug @ 1550' w/50 sx; 3rd plug @ 780' w/50 sx; 4th plug @ 360' w/10 sx; 5th plug @ 40' w/10 sx; rathole 15 sx; Total 225 sx 60-40 posmix 6% gel 1/4# floseal per sack.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No

If not explain why? Sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE# (316) 674-5768

ADDRESS 216 E. McFarland City/State Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 (company name) PHONE # (316) 262-1841 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Started @ 11:30 a.m. 5-22-93

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR AGENT

DATE: 6-8-93 AUTHORIZED OPERATOR/AGENT: [Signature] (signature)

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1993
CONSERVATION DIVISION
Wichita, Kansas