

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-071-20,476-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Yates Petroleum Corporation OPERATORS LICENSE NO. 30168
ADDRESS 105 South 4th Street, Artesia, NM 88210 PHONE # (505) 748-1471
LEASE (FARM) Blackburn WELL NO. #1 WELL LOCATION S/2-SW/4-SE/4 COUNTY Greeley
SEC. 36 TWP. 16S RGE. 43 (E) or (W) TOTAL DEPTH 5425 PLUG BACK TO Surface

Check One:

OIL WELL ☐ GAS WELL ☐ D & A ☒ SWD or INJ WELL ☐ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8 SET AT 622 CEMENTED WITH 175 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT N/A

CONDITION OF WELL: GOOD ☒ POOR ☐ CASING LEAK ☐ JUNK IN HOLE ☐

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL P & A by Halliburton with Class A Cement
as follows: Mud from 5425-2700, 50 sx @ 2700-2600; mud to 1660, 80 sx @ 1660-1560; mud to
650', 40 sx @ 650-550; mud to 40, 15 sx @ 40-0. 10 sx in Rathole, 10 sx in Mousehole.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN September 15, 1989, 1:00 AM on 9-15-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Pat Smith - Consultant (Murfin Drilling Co.) (719) 727-4516 - Pat Smith
PHONE # (316) 267-3241 - Murfin-Drlg.

ADDRESS 250 N. Water, Suite 300, Wichita, KS 67202

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 10-10-1989

ADDRESS Lamar, Colorado 50415 PHONE # (719) 336-7184

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED [Signature]
(Operator or Agent)

DATE: 10-5-89